

Tight Hole

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

(Other instructions on reverse side)

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. Type of Work

DRILL ☒DEEPEN ☐PLUG BACK ☐

b. Type of Well

Oil Well ☐(Gas Well ☒Other ☐Single Zone ☒Multiple Zone ☐

2. Name of Operator

MITCHELL ENERGY CORPORATION

3. Address of Operator

1670 Broadway - Suite 3200

Denver, CO 80202

4. Location of Well (Report location clearly and in accordance with any State requirements.)

1217' FWL & 863' FSL (SWSW)

At proposed prod. zone

same

14. Distance in miles and direction from nearest town or post office*

27⁺ miles southwest of Rangely, CO

15. Distance from proposed*

location to nearest property or lease line, ft.

863

(Also to nearest drlg. line, if any)

18. Distance from proposed location* to nearest well, drilling, completed, or applied for, on this lease, ft.

NA

16. No. of acres in lease

303.80

17. No. of acres assigned to this well

320

19. Proposed depth

6870'

20. Rotary or cable tools

rotary

21. Elevations (Show whether DF, RT, GR, etc.)

5820' GR

23.

PROPOSED CASING AND CEMENTING PROGRAM

Size of Hole	Size of Casing	Weight per Foot	Setting Depth	Quantity of Cement
12-1/4"	8-5/8"	24#, K-55, ST&C	800'	Circulate to surface
7-7/8"	4-1/2"	11.6#, K-55, LT&C	6870'	300 sx

The operator proposes to drill to a depth sufficient to test the Morrison for gas. If productive, 4-1/2" casing will be run and set at 6870'. If non-productive, the well will be plugged and abandoned in a manner consistent with State Regulations. The specific plans are attached in a Ten Point Program. Also attached are a Survey Plat, Location Layout, Well Location Map, and copy of a Blanket Drilling Bond for the State of Utah.

RECEIVED

JUL 09 1987

DIVISION OF
OIL, GAS & MINING

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

Signed

James C. Anderson
JAMES C. ANDERSON

Title DISTRICT PRODUCTION MANAGER

Date 7/2/87

(This space for Federal or State office use)

Permit No.

43-047-31802

Approval Date

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING

Approved by

Title

Conditions of approval, if any:


DATE: 7-14-87

BY: John R. Bays

WELL SPACING: 302-1

*See Instructions On Reverse Side

T 10 S, R 25 E, S.L.B. & M.



X = Section Corners Located

EXHIBIT #2
PROJECT

MITCHELL ENERGY CORP.

Well location, **HELLS HOLE STATE**
1 - 36 - 10 - 25, located as shown
in the S 1/2 S 1/2 Section 36, T 10 S,
R 25 E, S.L.B. & M. Uintah County, Utah.

BASIS OF ELEVATION

SPOT ELEVATION IN THE NE 1/4 SECTION 36, T10S,
R 25 E, S.L.B. & M TAKEN FROM THE WEAVER RIDGE,
UTAH - COLO. QUADRANGEL, UTAH COUNTY,
UTAH (TOPOGRAPHIC MAP) PUBLISHED BY THE
UNITED STATES DEPARTMENT OF THE INTERIOR,
GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED
AS BEING 6077 FEET.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM
FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY
SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE
BEST OF MY KNOWLEDGE AND BELIEF.

Lawrence L. Kay
REGISTERED LAND SURVEYOR
REGISTRATION NO 3137
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
P. O. BOX Q - 85 SOUTH - 200 EAST
VERNAL, UTAH - 84078

SCALE 1" = 1000'	DATE 6 / 15 / 87
PARTY R.K. D.A. BFW	REFERENCES GLO Plat
WEATHER Fair	FILE MITCHELL

July 7, 1987

RECEIVED
JUL 09 1987

UTAH DIVISION OF OIL, GAS AND MINING
355 West North Temple
#3 Triad Center - Suite 350
Salt Lake City, Utah 84180-1203

DIVISION OF
OIL, GAS & MINING

Attn: Ms. Arlene Solis

Re: APPLICATION FOR PERMIT TO DRILL
H.H. State #1-36-10-25
SWSW Sec. 36-T10S-R25E
Uintah County, Utah



Dear Ms. Solis:

The attached package contains an application for a Permit to Drill the Hell's Hole State #1-36-10-25 in Uintah County, Utah. The well as staked in Section 36 T10S-R25E will require approval as an exceptional location. The placing of the well in this location was made necessary by topographical restraints due to the canyon-mesa nature of the local topography. The well site selection was further limited by the fact that Section 36 is an irregular section that is truncated by the Colorado border. Mitchell Energy Corporation is the lease holder of all of Section 36 and also all the adjoining sections. Carol Kubly of your Vernal Office has inspected the location and concurs that it is the most accessible site.

The well will be an extension of the Hell's Hole Gas Field in western Rio Blanco County, Colorado. The well will be accessed for both vehicular traffic and for the pipeline connection from the existing Hell's Hole Field. The water will be hauled from the municipal source in Rangely, Colorado. Since the water is not from Utah it was determined by Bob Berger and Ted Baldwin of the Utah State Division of Water Resources that a State Water Permit is not necessary.

If you have any further questions or require additional information please contact Mr. Mark McNamee in our Denver Office.

Sincerely,

MITCHELL ENERGY CORPORATION

James C. Anderson

James C. Anderson
District Production Manager

JCA/MM/jms
Encl.

DRILLING PROGRAM

RECEIVED
JUL 09 1987

Attached to Form 9-331C
Mitchell Energy Corporation
H.H. State #1-36-10-25
SWSW Sec. 36-T10S-R25E, S.L.B. & M.
1217' FWL & 863' FSL
Uintah County, Utah

DIVISION OF
OIL, GAS & MINING

1. GEOLOGIC NAME OF SURFACE FORMATION:

The surface formation is the Wasatch.

2. ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:

Wasatch	Surface	Mancos "B"	3200'
Upper Sego	1810'	Niobrara	5215'
Anchor Tongue	2010'	Frontier	6240'
Lower Sego	2050'	Dakota Silt	6400'
Buck Tongue	2170'	Dakota	6470'
Castlegate	2340'	Morrison	6700'
Mancos	2580'		
TOTAL DEPTH	6870'		

3. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:

Castlegate	2340'	Possible water & Gas
Dakota	6470'	Gas
Morrison	6700'	Gas

No other formations are expected to give up oil, gas, or water in measurable quantities. If any shallow fresh water zones and/or coal zones are encountered, a D.V. tool will be inserted at 2580'± and cement will be circulated up across the zones of interest.

4. CASING PROGRAM:

Hole size	Interval	Section Length	Size (OD)	Weight, Grade And Joint	Condition
12-1/4"	0-800'	800'	8-5/8"	24# K-55 ST&C	New
7-7/8"	0-6870'	6870'	4-1/2"	11.6# K-55 LT&C	New

CEMENT PROGRAM:

Surface - Circulate to surface

Production - Approximately 300 sacks plus additives for producing interval. Shallow zone will be covered with cement using a DV tool placed below the Castlegate.

2. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

Refer to the descriptive layout of the blowout preventer and accompanying notes given in **Exhibit #1**.

The blowout preventer (BOP) will include two ram preventers (blind and 4-1/2" drill pipe) as shown in attached drawing "**Minimum Blowout Preventer Requirements - 3MWP**" and attached notes. The BOP's will be nipped up on the surface casing. The BOP's and accessory equipment will be hydraulically tested to 3000 PSI for thirty minutes prior to drilling out and after any use under pressure.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked each time the pipe is pulled out of the hole. These checks will be noted on the daily drilling reports. At least one kill line (2") will be installed below the BOP rams.

Accessories to the BOP equipment will include a kelly cock, drill string safety valve, drill string inside BOP and choke manifold with pressure rating equivalent to the BOP's.

All casing string will be pressure tested to 0.2 psi/ft or 1000 psi, whichever is the greater.

6. TYPES AND CHARACTERISTICS OF THE PROPOSED CIRCULATING FLUIDS:

The well will be drilled to total depth with a fresh water gel drilling mud. The properties of this fresh water gel system are:

<u>TYPE</u>	<u>MUD WEIGHT #/GAL.</u>	<u>VISCOSITY</u>	<u>WATER LOSS</u>
Low solids, non-dispersed	8.7-9.3	30-45	8-30 cc

Sufficient mud materials to maintain mud requirements and meet minimum lost circulation and blowout problems will be maintained at the wellsite.

7. AUXILIARY WELL CONTROL AND MONITORING EQUIPMENT:

- A. A kelly cock will be kept in the string.
- B. Bit floats will be used if lost circulation conditions do not exist.
- C. Visual monitoring of the drilling fluid system will be done. No special equipment will be needed to monitor the mud system.
- D. A full opening drill pipe stabbing valve with proper drill pipe fittings will be on the floor.

8. LOGGING, TESTING, AND CORING PROGRAM:

- A. Tests will be run on the basis of shows and on the recommendation of the geologist.
- B. The logging program will consist of Dual Induction-GR-SP, BHC-Sonic-GR, Density-Neutron, Circumferential Acoustic, and Structural Dipmeter from

below surface casing to total depth. Strata-Dip over Dakota interval and Mud Logger at 1000'.

- C. One 60 foot core in the upper Dakota.
- D. Stimulation procedures will be determined after evaluation of logs and well testing. If a treatment is indicated after perforating, the zone will be brokendown and a sand and foamed water frac will be performed on the prospective formation. The stimulation procedure will consist of approximately 2,000 gallons of 7.5% hydrochloric acid followed by a frac treatment of 17,000 gallons of gelled water with 120,000 pounds of 20/40 sand in 70% quality CO₂ foam.

9. **ABNORMAL CONDITIONS-PRESSURES-TEMPERATURES-POTENTIAL-HAZARDS:**


No abnormal pressures or temperatures are anticipated. Estimated temperature at 6870' is 160°F. Estimated bottom hole pressure (BHP) is 2000 psig.

No hydrogen sulfide or other hazardous fluids or gases have been encountered, reported or known to exist at these depths in this area.

10. **ANTICIPATED STARTING DATE AND DURATION OF OPERATIONS:**

Road and location work will begin as soon as approval has been received from the BLM. The anticipated spud date is August 1, 1987. Once commenced, the drilling operation should be finished within 25 days. If the well is productive, an additional 30 days will be required for completion.

Figure #1



NOTES REGARDING THE BLOW OUT PREVENTERS

1. Drilling nipple to be so constructed that it can be removed without use of a welder through rotary table opening, with minimum I.D. equal to preventer bore.
2. Wear ring to be properly installed in head.
3. Blow out preventer and all fittings must be in good condition 3000 psi W.P. minimum.
4. All fittings to be flanged.
5. Safety valves must be available on rig floor at all times with proper connections, valve to be full bore 3000 psi W.P. minimum.
6. All choke and fill lines to be securely anchored especially ends of choke lines.
7. Equipment through which bit must pass shall be at least as large as the diameter of the casing being drilled through.
8. Kelly cock or kelly.
9. Extension wrenches and hand wheels to be properly installed.
10. Blow out preventer control to be located as close to drillers position as feasible.
11. Blow out preventer closing equipment to include 30 gallon accumulator, two independent sources of pump power on each closing unit installation, and meet all API specifications.

SURFACE USE AND OPERATING PLAN

Attached to Form 9-331C
Mitchell Energy Corporation
H.H. State #1-36-10-25
SWSW Sec. 36 T10S-R25E, S.L.B & M.
1217' FWL & 863' FSL
Uintah County, Utah

1. EXISTING ROADS:

- A. The proposed well site and elevation plats are attached, **Exhibit #2**.
- B. Beginning on Main Street in Rangely, Colorado. Turn south at the stoplight and proceed 17.8 miles south on Dragon Trail Road to the Rabbit Mountain turnoff. Turn right on the Rabbit Mountain Road and proceed in a westerly direction for 4.8 miles to the Wexpro 7-1 location. Stay to the right and go 3.5 miles in a northwesterly direction down to Hell's Hole Canyon. Turn left in the canyon and proceed approximately 1.5 miles to the location.
- C. All roads to the location are shown in **Exhibit #3 & 3A**. The existing roads described above and illustrated by a red line are adequate for travel during the drilling and production activities. Upgrading of the road prior to drilling will be done where necessary as determined during the onsite.
- D. Not applicable.
- E. Existing roads, within a one-mile radius are shown on **Exhibit #4**.
- F. For existing roads, routine grading and upgrading of low water crossings where necessary will be conducted to maintain their condition.

2. PLANNED PIPELINE:

A pipeline is planned to be constructed to this well to connect the well to the Hell's Hole gathering system for marketing purposes. The pipeline will be a buried steel 6" schedule 40 pipeline. The pipeline will be wrapped and cathodically protected. The line will originate at a block valve on the east side of Section 3-T2S-R104W in Rio Blanco County, Colorado. There will be 1588' of 6" line inside Utah. There will also be approximately 40' of 3" lateral line to connect the gas separator to the collection system.

The pipeline will be located along the north side of the access road as shown on **Exhibit #3B**. The route has been flagged in the field by Uintah Engineering of Vernal, Utah.

3. LOCATION OF EXISTING WELLS:

For all existing wells within a one-mile radius of this development well, see **Exhibit #4.**

- A. There are no water wells within a one-mile radius.
- B. There are no abandoned well within a one-mile radius.
- C. There are no temporarily abandoned wells within a one-mile radius.
- D. There are no disposal wells within a one-mile radius.
- E. There are no wells presently being drilled within a one-mile radius.
- F. There is one producing well within a one-mile radius.
- G. There are no shut-in wells within a one-mile radius.
- H. There are no injection wells within a one-mile radius.
- I. There are no monitoring or observation wells for other uses within a one-mile radius.

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES:

- A. Owned or controlled by Lessee/Operator within 1 mile of Proposed Well:
 - (1) Tank Batteries: One tank battery at MEC's H. H. Federal #2-2-2-104.
 - (2) Production Facilities: Gas Separator at MEC's H.H. Federal #2-2-2-104.
 - (3) Oil Gathering Lines: None
 - (4) Gas Gathering Lines: Hell's Hole collection system.
 - (5) Injection Lines: None
 - (6) Disposal Lines: None
- B. If the well is productive, contemplated facilities will be as follows:
 - (1) Production facilities will be located on solid ground of the cut area of drill pad. All facilities will be contained on the well pad.
 - (2) Refer to **Exhibit #5** for the production facility layout.
 - (3) The tank battery will be constructed using a bulldozer to level the site, backhoes to dig trenches and bury lines, and pole trucks, floats, and roustabout crews to maneuver and set facility equipment. All flowlines and piping will be installed according to API specifications. Construction material will consist of surface soil. No additional material from outside sources is anticipated.

C. **Rehabilitation Plans:**

The plan for rehabilitation of the disturbed area no longer needed for operations after drilling and construction is completed is as follows:

1. The reserve pit will be backfilled after the contents of the pit are dry.
2. The area of the drill site not needed for production facilities will be recontoured to the natural level as nearly as possible and revegetated/reseeded by the contour method per specifications of the Bureau of Land Management.

- D. In the event that production is established, plans for permanent gas lines will be resubmitted to the appropriate agencies for approval.

5. **LOCATION AND TYPE OF WATER SUPPLY:**

- A. The primary source of water will be in Rangely, approximately 27 miles northeast of location
- B. Water will be hauled by tank truck to the drilling site.
- C. No water well will be drilled on this lease.

6. **SOURCE OF CONSTRUCTION MATERIALS:**

- A. No construction materials are anticipated to be needed for drilling the well or constructing the access roads into the location. Native soil will be utilized for the drilling site and access roads. If the surface soil materials are not sufficient, the required materials (rock, gravel, etc.) will be purchased from the dirt contractor.
- B. No construction materials will be taken from Federal lands.
- C. Native surface soil materials for construction of access roads are sufficient.
- D. **Exhibits #3, 3A and #4** show access roads crossing Federal lands. No Indian Land is involved.

7. **METHODS OF HANDLING WASTE DISPOSAL:**

- A. Cuttings not retained for evaluation purposes will be exhausted into the reserve pit (see **Exhibit #6** for location).
- B. Drilling fluids will be contained in steel mud tanks. The reserve pit will contain any excess flow from the well during drilling, cementing, and completion operations. The reserve pit will be an earthen pit, approximately 300'x30'x8' and fenced on three sides prior to drilling. Fenced on the 4th side immediately following rig removal.
- C. Produced water will be disposed into a reserve pit or a tank (depending on the rates). Produced oil will be collected in tanks or disposed into the reserve pit, depending on the volume and frequency of occurrence. If the volume of oil is sufficient, it will be trucked from the location. Water will be disposed of in

the reserve pit as per NTL-2B.

- D. A portable chemical toilet will be provided on the location for human waste.
- E. Garbage and trash produced during drilling or testing will be handled in the trash cage (see **Exhibit #6** for location). The garbage cage will be approximately 8'x8'x6' in size. This garbage will be hauled to the dump after drilling is completed. Water and tailings will be disposed into the reserve pit. Salts and other chemicals produced during drilling or testing will be disposed into the reserve pit. No toxic waste/chemicals will be produced by this proposed operation. If a trash cage is not available, a trash/burn pit will be constructed and fenced with woven wire.
- F. After the rig moves out, all materials will be cleaned up and no adverse materials will be left on location. The reserve pit will be fenced during drilling and kept closed until the pit has dried. All pits will be filled and the well site will be leveled and reseeded, per BLM specifications; this will occur when pits are dry enough to fill and as weather permits. Only that part of the pad required for producing facilities will be kept in use. In the event of a dryhole, only a dryhole marker will remain.

8. **ANCILLARY FACILITIES:**

No air strip, campsite or other facilities will be built during drilling and completion operations of this well.

9. **WELL SITE LAYOUT:**

- A. Refer to **Exhibit #6** for the Drill Pad layout as staked, with elevations by Uintah Engineering of Vernal, Utah. Cuts and fills have been indicated to show the planned cut across the proposed location. Topsoil will be stockpiled per BLM specifications to be determined at the pre-drill on-site inspection.
- B. Refer to **Exhibit #6** for a planned location diagram of the proposed rig and drilling equipment, reserve pit, trash cage, and pipe racks. No permanent living facilities are planned. There will be a trailer on site.
- C. The rig orientation, turn-around area, parking area, and access roads are shown in **Exhibit #6**.
- D. The reserve pit will not be lined.

10. **PLANS FOR RESTORATION OF SURFACE:**

- A. Upon completion of the proposed operations, and if the well is to be abandoned, the location will be backfilled, leveled, and contoured to as nearly the original topography as is feasible as soon as the pits have dried enough to handle earth moving equipment. The location will be reseeded per Bureau of Land Management recommendations. All spoils materials will be hauled to the dump upon completion of the drilling operation.
- B. Revegetation and rehabilitation will be achieved by re-seeding utilizing the contour method with a seed mixture of native grasses and shrubs recommended by the Bureau of Land Management.

- C. Three sides of the reserve pit will be fenced prior to drilling operations. Prior to rig release, the reserve pit will be fenced on the fourth side to prevent livestock or wildlife from being entrapped. The fencing will be maintained until leveling and the clean-up accomplished.
- D. If any oil is on the pits and cannot be immediately removed after operations cease, the pit containing the oil or other adverse substances will be overhead flagged and fenced. The entire location will be policed for trash and other refuse, and additional clean-up will be done as deemed necessary.
- E. Time to complete rehabilitation depends upon the time for pits to dry. Planting and revegetation should occur by Fall 1988, unless otherwise requested.

11. OTHER INFORMATION:

- A. The vegetation is sparse pinyon-juniper woodland, with abundant sage, cacti, grasses and narrow-leaved yucca.
- B. Geographically, the project area is 27 miles southwest of Rangely Colorado.
- C. There is not substantial live water in the immediate area. Evacuation Creek is located approximately 4 miles west of the the well.

The closest permanent residence is in Park Cayon approximately 5 miles southeast of the location.

- D. There are no reported restrictions or reservations noted on the oil and gas lease.
- E. Drilling is planned for August 1, 1987. It is anticipated that the casing point will be reached within 25 days after commencement of drilling.

12. LESSEE'S AND OPERATOR'S REPRESENTATIVE:

Mitchell Energy Corporation
3200 Amoco Building
1670 Broadway
Denver, CO 80202

(303) 861-2226


Mr. James C. Anderson


Ms. Joanie Seay

13. CERTIFICATION

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by Mitchell Energy Corporation and its contractors and subcontractors in conformity with this plan and the terms and conditions which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for this filing of a false statement.

Date: 7/7/87


Mr. James C. Anderson
District Production Manager



MITCHELL ENERGY CORP.

HELLS HOLE STATE #1-36-10-25

PROPOSED LOCATION


EXHIBIT

#3

TOPO.

MAP "A"

SCALE 1" = 4 MI.



**MITCHELL ENERGY CORP.
PROPOSED PIPELINE - R/W**

TOTAL LENGTH PIPELINE 2765'
TOTAL LENGTH 6" LINE 2725'
TOTAL LENGTH 6" LINE IN GOLD 1132'
TOTAL LENGTH 6" LINE IN UTAH 1588'
TOTAL LENGTH 3" LINE IN UTAH 40'

N

SCALE 1" = 2000'

Landing Strips

T-15
T-25

PROPOSED WELL

200' Hole


EXISTING WELL
HELLS HOLE FEB. 2-2-2-104

EXISTING PIPELINE

UTAH CO
RIO BLANCO CO



EXHIBIT #3B

JEEP





MITCHELL ENERGY CORPORATION
H.H. STATE #1-36-10-25

PRODUCTION PAD LAYOUT
EXHIBIT #5




MITCHELL ENERGY CORP.
HELLS HOLE STATE # 1-36-10-25

SCALES 1" = 50' HORIZ
1" = 10' VERT.
DATE 6-15-87



C
R
O
S
S

S
E
C
T
I
O
N
S



Scales
1" = 50'

APPROXIMATE YARDAGES

Cu. Yds. Cut - 7,319

Cu. Yds. Fill - 5,788

NOTE: THRU TRAFFIC TO
BE MAINTAINED
ACROSS LOCATION
DURING DRILLING

DRILLING LOCATION ASSESSMENT
State of Utah
Division of Oil, Gas & Mining

OPERATOR: Mitchell Energy Corporation WELL NAME: Hells Hole State 1-36-10-25
QTR/QTR: SWSW SECTION: 36 TWP: 10 South RANGE: 25 East
COUNTY: Uintah FIELD: Wildcat 1217' FW L 863' FS L
SFC OWNER: State of Utah LEASE #: _____
SPACING: _____ F SECTION LINE _____ F QTR/QTR LINE _____ F ANOTHER WELL
INSPECTOR: Carol A. Kubly DATE & TIME: 1:30 p.m. 11 June 1987
PARTICIPANTS: Mark McNamee w/ Mitchell Energy, Robert Kay & Don Allred w/ Uintah
Engineering

REGIONAL SETTING/TOPOGRAPHY:

Uintah Basin of the Colorado Plateau, Hells Hole Canyon

LAND USE

CURRENT SURFACE USE: Open Range, Sheep and Deer grazing

PROPOSED SURFACE DISTURBANCE: 300' by 220' for location. Access road in existence

AFFECTED FLOODPLAINS AND/OR WETLANDS: Not Applicable

FLORA/FAUNA: Indian rice grass, cheat grass, grease wood, sage brush, sego lilys, prickly pear, daisys, orange flowers, gnats, mosquitos, lizards, rattle snakes, ants

ENVIRONMENTAL PARAMETERS

GEOLOGY

SOIL TYPE AND CHARACTERISTICS: Light to medium brown clayey to silty sand

SURFACE FORMATION & CHARACTERISTICS: Green River formation - tan to light brown sandstone - argillaceous in part.

EROSION/SEDIMENTATION/STABILITY: Appears stable - no unforeseen changes

SUBSURFACE GEOLOGY

OBJECTIVE(S)/DEPTH(S): Morrison Formation at 6870' - proposed T.D.

ABNORMAL PRESSURES - HIGH AND LOW: LCZ about 2200' (above Castlegate Fm.)

CULTURAL RESOURCES/ARCHAEOLOGY: to be done by Nikens & Associates - Montrose, CO.

WATER RESOURCES: Hells Hole Canyon intermittent drainage will be abutted by the proposed location.- no reroute necessary. Small intermittent wash across location.

RESERVE PIT

CHARACTERISTICS: 30' wide by 300' long by 8' deep to be located on the North side of proposed location.

LINING: None necessary.

MUD PROGRAM: Low solids non-dispersed bentonite / gel / fresh water.

DRILLING WATER SUPPLY: _____

OTHER OBSERVATIONS:

STIPULATIONS FOR APD APPROVAL:


1. Stay out of main drainage
2. Pipeline routed along south side of access road.
3. Topsoil stockpile in southeast corner.

ATTACHMENTS

Mitchell Energy Corp.
Hells Hole State 1-36-10-25
SWSW Sec 36 T10S, R25E
Uintah County, Utah



Ridge Top



by: Carol Kubly

DOUBLE JACK TESTING & SERVICES, INC.

B.O.P. Test Report

B.O.P. Test Performed on (date) October 1, 1987

43-047-31802

Oil Company Mitchel

Well Name & Number H H Federal 2-14 2-104

Section 36

101505

Township 10S

Range 25E

County Uintah, Utah

Drilling Contractor Grace #179

Oil Company Site Representative C.L. Cruth

Pig Tool Pusher

Tested out of Vernal, Utah

Notified Prior to Test Bill Kraft/B.L.M. witnessed test

Copies of This Test Report Sent to: Site Representative

B.L.M./Bill Kraft/Meeker, CO.

Utah Oil & Gas

Original Chart & Test Report on File at: Double Jack office in

Vernal, Utah

Tested by: Double Jack Testing & Services, Inc.
108 Parkview Road
P.O. Box 2097
Evanston, Wyoming 82930

Double Jack Testing & Services, Inc.
608 North Vernal Ave.
Vernal, Utah 84078

RECEIVED
OCT 13 1987

DIVISION OF
OIL, GAS & MINING

Double Jack Testing & Services Inc.

P.O. Box 2097

Evanston, Wyoming 82930

(307) 789-9213

FIELD

TICKET 5300

DATE

10-1-87

OPERATOR

MITCHEL

RIG NAME AND #

BK TO GRACE

GRACE LLC 179

WELL NAME AND NO.

HH FED 2-14 - 2-10

COUNTY

STATE

SECTION

TOWNSHIP

RANGE

Conch

Utah

36

10 S

25 E

EQUIPMENT TESTED

RAMS 3000 PSI (TOP RAMS)

RAMS 3000 PSI

RAMS

ANNULAR B.O.P. TESTED @ 2000 PSI HAD TO CHANGE OUT ONE

CHOKER LINE 3000

KILL LINE 3000

UPPER KELLY 3000

LOWER KELLY 3000

SAFETY VALVES 3000

ADDITIONAL TESTS & COMMENTS

BIM HAND ON LOCATION - BILL KRAFT witnessed tests and numerous leaks on equipment but all repaired except 2nd MAIN ON CORKERAGE ON MAIN BLOWER which BILL said wasn't needed. had an internal leak on it not exterior.

CLOSING UNIT PSI

CLOSING TIME OF RAMS

HYDRIL

CLOSED CASING HEAD VALVE

4/2

SET WEAR RING

NO

COMPANY		LEASE AND WELL NAME #	DATE OF TEST	RIG # AND NAME
MITCHELL		HH FED 2-14-2-104	10-1-87	GRACE RIG 179
ST#	TIME			
	2:30 ^{pm} - 4:15 ^{pm}	LOAD TOOL & TRAVEL TO RIG FROM EVANSTON WELDER welding wellhead when I arrived		
	4:15 - 5:15	Pick up Kelly & Rig up to test while welder was finishing wellhead		
	5:15 - 5:22	Attempt to test lower Kelly cock over-d up & work Kelly cock retest no test at this time		
	5:22 - 5:58	TEST UPPER KELLY COCK @ 3000 PSI had to pressure up twice OK		
	6:02 - 6:18	RETEST OF #1 LOWER KELLY COCK PUMPED UP TWICE OK		
	6:18 - 6:55	RIG UP TO TEST CHOKER MANIFOLD WORK VALVES STIFF		
	6:55 - 7:08	TEST INSIDE MANUAL VALVES ON CHOKER MANIFOLD & 2ND MANUAL ON CHOKER VALVE (ORIGINAL VALVE LEAKED SWITCHED BACK TO 3RD VALVE ON CHOKER LINE)		
4	7:08 - 7:25	TESTED INSIDE MANUAL VALVES ON CHOKER MANIFOLD & 3RD VALVE ON CHOKER LINE		
5	7:25 - 7:55	ATTEMPT TO TEST OUTSIDE MANUAL VALVE ON CHOKER manifold on main blocky line No test at this time		
6	7:55 - 8:12	TESTED MANUAL CHOKER OK		
	8:12 - 11:55	FINISH WIPING UP BOPS & HOOKING UP ACCUMULATOR LINES MAKE UP TEST EQUIP. SET PLUG FILL BOPS, HAD TO WAIT FOR BOLTS FOR BOPS		
7	11:55 ^{pm} - 1:15 ^{am}	ATTEMPT TO TEST BOPS LEAK ON KILLING TIGHTEN UP BOLTS ON FLANGE BOLTS DIFFERENT SIZES NO WRENCHES ON RIG TO FIT ALL OF THEM HAD TO USE CRESSENT WRENCHES		
7	1:15 ^{am} - 1:31 ^{am}	ATTEMPT TO TEST PIPE RAMS & INSIDE MANUAL VALVE ON KILLING & 3RD MANUAL VALVE ON CHOKER LINE PIPE RAMS & MANUAL VALVE OK		
	1:31 - 4:57 ^{am}	but Flange was still seeping SHUT DOWN TO CHANGE OUT BOLTS IN FLANGE HAD TO GRIND THEM OFF		
8	4:57 - 5:15	Pipe Rams, outside manual valve on Killing & 2nd manual valve on choke line		
	5:13 - 5:			
9	5:24 - 5:39	PIPE RAMS INSIDE MANUAL ON CHOKER LINE & OUTSIDE MANUAL ON KILLING OK		
	5:49 - 6:05	Pipe Rams & vertical valve on choke manifold		
11	6:05 ^{pm} - 1:10 ^{pm}	ATTEMPT TO TEST HYDRIL LEAK ON ROW TIGHTEN RUBBER LEAKED PRESSURED UP & WORKED A LOT NO TEST, WAITED FOR HYDRIL TO COME FROM STACKED RIG. WENT TO BREAKFAST		
12	1:15 - 1:30	PUT CHART 3 BACK ON RECORDER TO FILL OUT TESTED BLIND RAMS WITH HYDRIL OFF AND CHECK VALVE OK		

COMPANY

LEASE AND WELL NAME #

DATE OF TEST

RIG # AND NAME

TEST #

TIME

13

1:33 - 1:48

1:48^{PM} - 2:40^{AM}

TESTED PART VALVE ONLY

Wait on hydril to arrive, slept till it arrived, had to
BREAK OFF BOPS came with full set of BOPS made up set on
Sub & nipped up

11

2:40 - 3:15


TESTED HYDRIL & CHECK VALVE AGAIN WHILE RESETING VALVES
ON CHOKELINE & DRAINING CHOKER MANIFOLD


3:15 - 6:30


RIGGED DOWN & DROVE TO UCCENA


DID NOT SET WEAR RING


DOUBLE JACK
TESTING & SERVICES, INC.
P.O. Box 2097
Evanston, Wyoming 82930
(307) 789-9214











CONFIDENTIAL

CONFIDENTIAL
PERIOD
EXPIRED

07/13/87

ON 1-22-89

OPERATOR Mitchell Energy DATE 7-13-87

WELL NAME Hell's Hole State 1-36-10-25

SEC SWSW 36 T 10S R 25E COUNTY Uintah

43-047-31802
API NUMBER

State
TYPE OF LEASE

CHECK OFF:

☒

PLAT

☒

BOND

☒

NEAREST
WELL

☒

LEASE

☒

FIELD

☒

POTASH OR
OIL SHALE

PROCESSING COMMENTS:

No other well in Sec. 36

Water - Rangely, Co.

Exception requested

APPROVAL LETTER:

SPACING: ☐ 203 _____ UNIT

☐ 302

☐

CAUSE NO. & DATE

☒

302.1

STIPULATIONS:

1- State history

~~2- The location shall be constructed to avoid disturbance of the Hell's Hole Canyon main drainage located to the south of the ^{proposed} well.~~

~~3- The topsoil stockpile for the location should be located to the southeast of the well location.~~



STATE OF UTAH
NATURAL RESOURCES
Oil, Gas & Mining

Norman H. Bangerter, Governor
Dee C. Hansen, Executive Director
Dianne R. Nielson, Ph.D., Division Director

355 W. North Temple • 3 Triad Center • Suite 350 • Salt Lake City, UT 84180-1203 • 801-538-5340

July 14, 1987

Mitchell Energy Corporation
1670 Broadway, Suite 3200
Denver, Colorado 80202

Gentlemen:

Re: Hell's Hole State 1-36-10-25 - SW SW Sec. 36, T. 10S, R. 25E
863' FSL, 1217' FWL - Uintah County, Utah

Approval to drill the referenced well is hereby granted in accordance with Rule 302.1, Oil and Gas Conservation General Rules, subject to the following stipulations:

1. Prior to any ground-disturbing activity on state lands or lands owned or controlled by the state or its subdivisions, a cultural resource clearance report must be filed with and approved by the Division of State History, phone (801) 533-4563. A list of acceptable archaeological contractors is available from the Division of State History.

In addition, the following actions are necessary to fully comply with this approval:


1. Spudding notification to the Division within 24 hours after drilling operations commence.
2. All well operators are responsible for sending an Entity Action Form to the Division of Oil, Gas and Mining within five working days of the time that a new well is spudded or a change in operations or interests necessitates a change in Entity status.
3. Submittal to the Division of completed Form OGC-8-X, Report of Water Encountered During Drilling.
4. Prompt notification to the Division should you determine that it is necessary to plug and abandon this well. Notify John R. Baza, Petroleum Engineer, (Office) (801) 538-5340, (Home) 298-7695, or R. J. Firth, Associate Director, (Home) 571-6068.

Page 2
Mitchell Energy Corporation
Hell's Hole State 1-36-10-25
July 14, 1987

5. Prior to commencement of the proposed drilling operations, plans for toilet facilities and the disposal of sanitary waste at the drill site shall be submitted to the local health department having jurisdiction. Any such drilling operations and any subsequent well operations must be conducted in accordance with applicable state and local health department regulations. A list of all local health departments and copies of applicable regulations are available from the Division of Environmental Health, Bureau of General Sanitation, telephone (801) 533-6163.
6. This approval shall expire one (1) year after date of issuance unless substantial and continuous operation is underway or an application for an extension is made prior to the approval expiration date.

The API number assigned to this well is 43-047-31802.

Sincerely,



R. J. Firth
Associate Director, Oil & Gas

as
Enclosures
cc: Division of State Lands & Forestry
Branch of Fluid Minerals
D. R. Nielson
8159T

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

(FORM 9-329)

(2/76)

OMB 42-RO 356

MONTHLY REPORT
OF
OPERATIONS

Lease No. 4-0452-1 *Dug*

Communitization Agreement No. _____

Field Name Hell's Hole Field

Unit Name 43-047-31800

Participating Area _____

County Uintah County State Utah

Operator Mitchell Energy Corporation

☐ Amended Report

090904

The following is a correct report of operations and production (including status of all unplugged wells) for the month of August, 1987

(See Reverse of Form for Instructions)

This report is required by law (30 U.S.C. 189, 30 U.S.C. 359, 25 U.S.C. 396 d), regulation (30 CFR 221.60), and the terms of the lease. Failure to report can result in the assessment of liquidated damages (30 CFR 221.54 (j)), shutting down operations, or basis for recommendation to cancel the lease and forfeit the bond (30 CFR 221.53).

Well No.	Sec. & 1/4 of 1/4	TWP	RNG	Well Status	Days Prod.	*Barrels of Oil	*MCF of Gas	*Barrels of Water	Remarks
1-36-10-25	Sec. 36 SWSW	T10S	R25E	Bldg Location					

RECEIVED
SEP 8 1987

DEPARTMENT OF OIL
AND GAS

*If none, so state.

DISPOSITION OF PRODUCTION (Lease, Participating Area, or Communitized Area basis)

	Oil & Condensate (BBLs)	Gas (MCF)	Water (BBLs)
*On hand, Start of Month	_____	XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX
*Produced	_____	_____	_____
*Sold	_____	_____	XXXXXXXXXXXXXXXXXX
*Spilled or Lost	_____	XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX
*Flared or Vented	XXXXXXXXXXXXXXXXXX	_____	XXXXXXXXXXXXXXXXXX
*Used on Lease	_____	_____	XXXXXXXXXXXXXXXXXX
*Injected	_____	_____	_____
*Surface Pits	XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX	_____
*Other (Identify)	_____	_____	_____
*On hand, End of Month	_____	XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX
*API Gravity/BTU Content	_____	_____	XXXXXXXXXXXXXXXXXX

Authorized Signature: James C. Anderson Address: 1670 Broadway Suite 3200 Denver,
Title: District Production Manager Page 1 of 1 CO. 80202

UNITED STATES
DEPARTMENT OF THE INTERIOR
- GEOLOGICAL SURVEY
(FORM 9-329)
(2/76)
OMB 42-RO 356

MONTHLY REPORT
OF
OPERATIONS

Lease No. ML-4267
Communitization Agreement No. _____
Field Name Hell's Hole Field 101311
Unit Name 43-047-31800
Participating Area _____
County Uintah County _____ State Utah
Operator Mitchell Energy Corporation
☐ Amended Report

The following is a correct report of operations and production (including status of all unplugged wells) for the month of September, 19 87

(See Reverse of Form for Instructions)

This report is required by law (30 U.S.C. 189, 30 U.S.C. 359, 25 U.S.C. 396 d), regulation (30 CFR 221.60), and the terms of the lease. Failure to report can result in the assessment of liquidated damages (30 CFR 221.54 (j)), shutting down operations, or basis for recommendation to cancel the lease and forfeit the bond (30 CFR 221.53).

Well No.	Sec. & 1/4 of 1/4	TWP	RNG	Well Status	Days Prod.	*Barrels of Oil	*MCF of Gas	*Barrels of Water	Remarks
<u>HELL'S HOLE STATE</u> #1-36-10-25	Sec. 36 SWSW	10S	R25W	WOCU	0	0	0	0	

9/1/87: Spud well 1300 hrs. 9/2/87: Drilling to 802'. 9/3/87: Set 8-5/8" csg @ 802'. Cement w/560 sx. 9/4-23/87: Drilling 802'-6830'. 9/24/87: Logging and POOH. 9/25/87: Run 4-1/2" csg. Cement w/1905 sx. Release rig. WOCU. 9/26-30/87: Preparing completion plans.

RECEIVED

OCT 7 1987

DIVISION OF OIL
GAS & MINING

*If none, so state.

DISPOSITION OF PRODUCTION (Lease, Participating Area, or Communitized Area basis)

	Oil & Condensate (BBLs)	Gas (MCF)	Water (BBLs)
*On hand, Start of Month	_____	XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX
*Produced	_____	_____	_____
*Sold	_____	_____	XXXXXXXXXXXXXXXXXX
*Spilled or Lost	_____	XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX
*Flared or Vented	XXXXXXXXXXXXXXXXXX	_____	XXXXXXXXXXXXXXXXXX
*Used on Lease	_____	_____	XXXXXXXXXXXXXXXXXX
*Injected	_____	_____	_____
*Surface Pits	XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX	_____
*Other (Identify)	_____	_____	_____
*On hand, End of Month	_____	XXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXX
*API Gravity/BTU Content	_____	_____	XXXXXXXXXXXXXXXXXX

Authorized Signature: Albert R. Hunt Address: 1670 Broadway Suite 3200 Denver,
Title: District Engineer Page 1 of 1 CO

October 28, 1987



State of Utah Natural Resources
Oil, Gas & Mining
355 W. North Temple
3 Triad Center - Suite 350
Salt Lake City, Utah 84180-1203

Attn: Arlene Solis

Re: Reports: Entity Action Form and
Water Encountered During Drilling

Dear Arlene:

Please find enclosed the above referenced reports for the H.H. State 1-36-10-25 located in Uintah County, Utah.

Should you have any questions, please feel free to contact me.

Sincerely,

MITCHELL ENERGY CORPORATION

Joanie Seay
Joanie Seay
Engineer Technician

RECEIVED
OCT 30 1987

DIVISION OF
OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING
3 TRIAD CENTER, SUITE 350
SALT LAKE CITY, UT 84180-1203

110422

REPORT OF WATER ENCOUNTERED DURING DRILLINGWell Name & Number H.H. State 1-36-10-25

43-047-31800

Operator MITCHELL ENERGY CORPORATION Address 1670 Broadway-Suite 3200, Denver 80202Contractor Grace Rig #179 Address 2801 Youngfield St-#178, Golden 80201Location SW 1/4 SW 1/4 Sec. 36 T. 10S R. 25E County UintahWater Sands

<u>Depth</u>		<u>Volume</u>	<u>Quality</u>
From	To	Flow Rate or Head	Fresh or Salty
1. _____			
2. _____			
3. _____			
4. _____			
5. _____			

(Continue on reverse side if necessary)

Formation TopsRemarks NO WATER WAS ENCOUNTERED WHILE DRILLING

NOTE: (a) Report on this form as provided for in Rule 806, Oil and Gas Conservation General Rules.

(b) If a water analysis has been made of the above reported zone, please forward a copy along with this form.

RECEIVED
OCT 30 1987DIVISION OF
OIL, GAS & MINING

WELL COMPLETION OR RECOMPLETION REPORT AND LOG *

1a. TYPE OF WELL:		OIL WELL <input type="checkbox"/>	GAS WELL <input checked="" type="checkbox"/>	DRY <input type="checkbox"/>	Other <input type="checkbox"/>
b. TYPE OF COMPLETION:		NEW WELL <input checked="" type="checkbox"/>	WORK OVER <input type="checkbox"/>	DEEP-EN <input type="checkbox"/>	PLUG BACK <input type="checkbox"/>
				DIFF. RESVR. <input type="checkbox"/>	Other <input type="checkbox"/>
2. NAME OF OPERATOR MITCHELL ENERGY CORPORATION					
3. ADDRESS OF OPERATOR 1670 Broadway - Suite 3200 Denver, CO 80202					
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements) At surface 1217' FWL & 863' FSL (SWSW) At top prod. interval reported below same At total depth same					
14. PERMIT NO. 43-047-31802		DATE ISSUED 7/14/87			

5. LEASE DESIGNATION AND SERIAL NO.

State of Utah-ML 42673

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

NA 110401

7. UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

H. STATE

9. WELL NO.

1-36-10-25

10. FIELD AND POOL, OR WILDCAT

Wildcat

11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA

Sec. 36-T10S-R25E

12. COUNTY OR PARISH

Uintah

13. STATE

UT

15. DATE SPUDDED 9/1/87	16. DATE T.D. REACHED 9/23/87	17. DATE COMPL. (Ready to prod.) 10/22/87	18. ELEVATIONS (DF, RES, RT, GR, ETC.)* 5820 GR	19. ELEV. CASINGHEAD
20. TOTAL DEPTH, MD & TVD 6830'	21. PLUG, BACK T.D., MD & TVD 6712'	22. IF MULTIPLE COMPL., HOW MANY* NA	23. INTERVALS DRILLED BY →	ROTARY TOOLS 0-6830
24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)* 6467'-6505' (OA)				25. WAS DIRECTIONAL SURVEY MADE no
26. TYPE ELECTRIC AND OTHER LOGS RUN DIL/Acoustic/GR, CNL/FDC/GR				27. WAS WELL CORRED. yes

28. CASING RECORD (Report all strings set in well)				
CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD
8-5/8"	24#, K-55, ST&C	802'	12-1/4"	560 SX
4-1/2"	11.6#, K-55, LT&C	6830'	7-7/8"	1480 SX

29. LINER RECORD					30. TUBING RECORD		
SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
							6347

31. PERFORATION RECORD (Interval, size and number)		32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.	
6490'-6505'	2 JSFP - 31 holes - 0.36"	DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
6467'-6489'	2 JSFP - 68 holes	6490'-6505'	1500 gals 7-1/2% HCL
		6467'-6505'	3000 gals 7-1/2% HCL
			Frac'd w/25,800 gal 70.0 CO ₂ foam
			w/66,000# 20/40 sand

33. PRODUCTION							
DATE FIRST PRODUCTION NA		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)				WELL STATUS (Producing or shut-in) SI	
DATE OF TEST 10/22/87	HOURS TESTED 6	CHOKE SIZE 3/4	PROD'N. FOR TEST PERIOD →	OIL—BBL. 8	GAS—MCF. 3509 MCFD	WATER—BBL. 15	GAS-OIL RATIO
FLOW. TUBING PRESS. 1000	CASING PRESSURE 0	CALCULATED 24-HOUR RATE →	OIL—BBL. 32	GAS—MCF. 3509	WATER—BBL. 45	OIL GRAVITY-API (CORR.) 30	
34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) FLARED						TEST WITNESSED BY G. COOPER	

35. LIST OF ATTACHMENTS

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

JAMES C. ANDERSON

TITLE

DISTRICT PRODUCTION MANAGER

DATE 10/30/87

*(See Instructions and Spaces for Additional Data on Reverse Side)

INSTRUCTIONS

General: This form is designed for submitting a complete and correct well completion report and log on all types of lands and leases to either a Federal agency or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office. See instructions on items 22 and 24, and 33, below regarding separate reports for separate completions.

If not filed prior to the time this summary record is submitted, copies of all currently available logs (drillers, geologists, sample and core analysis, all types electric, etc.), formation and pressure tests, and directional surveys, should be attached hereto to the extent required by applicable Federal and/or State laws and regulations. All attachments should be listed on this form, see item 35.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 18: Indicate which elevation is used as reference (where not otherwise shown) for depth measurements given in other spaces on this form and in any attachments items 22 and 24. If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) (if any) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

Item 29: "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

Item 33: Submit a separate completion report on this form for each interval to be separately produced. (See instruction for items 22 and 24 above.)

37. SUMMARY OF POROUS ZONES:

SHOW ALL IMPORTANT ZONES OF POROSITY AND CONTENTS THEREOF; CORED INTERVALS; AND ALL DRILL-STEM TESTS, INCLUDING DEPTH INTERVAL TESTED, CUSHION USED, TIME TOOL OPEN, FLOWING AND SHUT-IN PRESSURES, AND RECOVERIES

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.
Dakota	6461	6518	Cored 57' - recovered 48'. Sst w/vf fn gr. sl. shy.

38.

GEOLOGIC MARKERS

NAME	TOP	
	MEAS. DEPTH	TRUE VERT. DEPTH
Upper Sego	1844	
Anchor Tongue	2006	
Lower Sego	2044	
Buck Tongue	2142	
Castlegate	2326	
Mancos	2564	
Mancos "B"	3190	
Niobrara	5210	
Frontier	6239	
Dakota Silt	6396	
Dakota	6467	
Morrison	6708	
TOTAL DEPTH	6870	

December 21, 1987

RECEIVED
DEC 24 1987

DIVISION OF
OIL, GAS & MINING

122901



Utah Division of Oil, Gas & Mining
3 Triad Center - Suite 350
Salt Lake City, Utah 84180-1203

Attn: John Baza

10 S 25 E SEC 36 SEW-DKTA

43-047-31802

Re: Hell's Hole State 1-36-10-25
Uintah County, Utah

Dear John:

Please find enclosed the attached well test data from the subject well. This information is being submitted to comply with Rule #311, however we request that you keep the information confidential.

Sincerely,

N7580

MITCHELL ENERGY CORPORATION

James C. Anderson

James C. Anderson
District Production Manager

JCA/jms
Encl.

RECEIVED

DEC 24 1987

DIVISION OF
OIL, GAS & MINING

TEFTELLER, INC.
RESERVOIR ENGINEERING DATA
MIDLAND, TEXAS

WELL : HELL'S HOLE STATE NO. 1-36-10-25

PAGE 1 OF 7

FIELD : HELL'S HOLE

FILE 4-19235-FT&BU

CHRONOLOGICAL PRESSURE AND PRODUCTION DATA

1987 DATE	STATUS OF WELL	TIME	ELAPSED TIME		LOG	T+ΔT ΔT	DAILY RATE		WELLHEAD PRESSURE		BHP @ 6500' PSIG
			HRS.	MIN.			OIL B/D	GAS MCF/D	TBG	CSG	
10-27	Arrived on location										
	Well shut-in	08:45									
	Rig up tandem BHP equipment, run in hole with dummy tools (1½"x8')										
	TD at 6593' KB	10:00									
	Tandem gradient traverse	11:10							1821	Pkr	
	Off bottom with instruments	12:10							1821		2153
	Open slightly to supply heat to unit	13:00									
	Open	13:45	0	00							
		14:00	0	15				976.4	1144		
		14:15	0	30				860.2	673		
	Fluid to surface										
		14:19	0	34							
		14:30	0	45				338.4	1258		
		14:45	1	00				822.8	1408		
		15:00	1	15				860.2	1340		
	Shut-in (unit not handling fluid)										
	Adjust fluid dumps	15:00	0	00							
	Open	15:45	0	00					1598		
		16:00	0	15				924.5	1502		
	Fluid to surface	16:15	0	30				710.5	1440		
		16:30	0	45				832.6	1293		
		16:45	1	00				740.0	1352		
		17:15	1	30				876.0	1395		
		17:45	2	00				847.8	1420		
		18:45	3	00				832.6	1418		
	Fluid surging, clean choke periodically to maintain rate										
		19:45	4	00				785.6	1412		
		20:45	5	00				732.3	1440		
		21:45	6	00				692.4	1486		
		22:45	7	00				757.0	1432		
		23:45	8	00				656.7	1480		

TEFTELLER, INC.
RESERVOIR ENGINEERING DATA
MIDLAND, TEXAS

WELL : HELL'S HOLE STATE NO. 1-36-10-25

PAGE 2 **OF** 7

FIELD : HELL'S HOLE

FILE 4-19235-FT&BU

CHRONOLOGICAL PRESSURE AND PRODUCTION DATA

1987 DATE	STATUS OF WELL	TIME	ELAPSED TIME		LOG	$\frac{T+\delta T}{\delta T}$	DAILY RATE		WELLHEAD PRESSURE		BHP @ 6500' PSIG
			HRS.	MIN.			OIL B/D	GAS MCF/D	TBG	CSG	
10-28		00:45	9	00				690.8	1385		
	Clear choke	01:45	10	00				689.4	1550		
	Clear choke	03:45	12	00				631.3	1485		
	Clear choke	05:45	14	00				508.0	1605		
	Raise separator temperature										
		07:15	15	30							
	Clear choke	07:45	16	00				914.0	1185		
		09:45	18	00				1207.3	1467		
		11:45	20	00				1280.8	1442		
		13:45	22	00				1278.9	1425		
	Meter run gas samples take by Mountain Fuel Employee	14:45	23	00							
		15:45	24	00							
		17:45	26	00			38.0	1254.4	1458		
		19:45	28	00				1215.4	1425		
		21:45	30	00				1246.6	1438		
10-29		23:45	32	00				1221.2	1436		
		01:45	34	00				1235.7	1427		
		03:45	36	00				1225.3	1422		
		05:45	38	00				1241.0	1421		
		07:45	40	00				1242.6	1392		
								1240.4	1411		
	Instruments @ 6500' KB*	09:45	42	00				1227.7	1417		1834
		11:45	44	00				1227.1	1374		1831
		13:45	46	00				1255.0	1380		1826
	Collect samples gas, oil and water	15:45	48	00							
		18:00	50	15			29.0	1270.5	1392		1823
								1258.6	1381		1819
	Shut-in for buildup	18:00	0	00							
		18:15	0	15		2.299					1951
		18:30	0	30		2.000			1614		1973
		18:45	0	45		1.826					1983
		19:00	1	00		1.703			1659		1989

*very thick paraffin in tubing from 0-550', thick to 1100'

TEFTELLER, INC.
RESERVOIR ENGINEERING DATA
MIDLAND, TEXAS

WELL : HELL'S HOLE STATE NO. 1-36-10-25

PAGE 3 **OF** 7

FIELD : HELL'S HOLE

FILE 4-19235-FT&BU


CHRONOLOGICAL PRESSURE AND PRODUCTION DATA

1987 DATE	STATUS OF WELL	TIME	ELAPSED TIME		LOG	T+ δ T δ T	DAILY RATE		WELLHEAD PRESSURE		BHP @ 6500' PSIG
			HRS.	MIN.			OIL B/D	GAS MCF/D	TBG	CSG	
10-29		19:30	1	30		1.531					1995
		20:00	2	00		1.411					1998
		21:00	3	00		1.243					2002
		22:00	4	00		1.126					2004
10-30		00:00	6	00		0.966					2007
		02:00	8	00		0.857					2010
		04:00	10	00		0.775					2013
		06:00	12	00		0.710					2015
		10:00	16	00		0.612					2019
		14:00	20	00		0.541					2024
		18:00	24	00		0.486					2034
		22:00	28	00		0.442					2044
10-31		02:00	32	00		0.406					2052
		06:00	36	00		0.376					2058
		10:00	40	00		0.350					2064
		14:00	44	00		0.327					2070
		18:00	48	00		0.308					2076
		22:00	52	00		0.290					2080
11-1		02:00	56	00		0.275					2083
		06:00	60	00		0.261					2086
		10:00	64	00		0.249					2089
		14:00	68	00		0.238					2092
		18:00	72	00		0.227					2095
		02:00	80	00		0.209					2100
11-2		12:00	90	00		0.190					2104
		22:00	100	00		0.175					2107
		08:00	110	00		0.161					2110
11-3		10:00	120	00		0.150					2113
		04:00	130	00		0.140					2115
11-4		14:00	140	00		0.131					2117
		00:00	150	00		0.124					2118
11-5		10:00	160	00		0.117					2120
		20:00	170	00		0.111					2121
		12:00	186	00		0.102					2124
11-6	Gradient traverse								1784	Pkr	

TEFTELLER, INC.
Reservoir Engineering Data
P.O. Box 5247
Midland, Texas 79704

BUILDUP CURVE

Mitchell Energy Corporation
Hell's Hole State No. 1-36-10-25
File No. 4-19125-FT&BU



TEFTELLER, INC.

Reservoir Engineering Data
P.O. Box 5247
Midland, Texas 79704


BUILDUP CURVE

Mitchell Energy Corporation
Hell's Hole State No. 1-36-10-25
File No. 4-19125-FT&BU

$T = 49.5$ hours
 $p^* = 2146$ psig
 $m = 220.4$ psi/cycle
 $r^2 = 0.9976$

$\text{LOG } \frac{T+\Delta t}{\Delta t}$

bottomhole pressure at 6500 feet, psig






Company MITCHELL ENERGY CORPORATION Lease HELL'S HOLE STATE Well No. 1-36-10
Field HELL'S HOLE County UNITAH State UTAH
Formation DAKOTA Test Date OCTOBER 27, 1987

Status of Well Shut-in		
DEPTH	PRESSURE	GRADIENT
Feet	Psig	Psi/Ft.
0	1821	
1000	1877	0.056
2000	1930	0.053
3000	1983	0.053
4000	2032	0.044
5000	2080	0.048
5500	2104	0.048
5600	2109	0.050
5700	2113	0.040
5800	2118	0.050
5900	2123	0.050
6000	2128	0.050
6100	2133	0.050
6200	2137	0.040
6300	2142	0.050
6400	2147	0.050
6500	2153	0.060

PRESSURE POUNDS PER SQUARE INCH GAUGE






Company MITCHELL ENERGY CORPORATION Lease HELL'S HOLE STATE Well No. 1-36-10
Field HELL'S HOLE County UNITAH State UTAH
Formation DAKOTA Test Date NOVEMBER 6, 1987

Status of Well Shut-in 186 hours		
DEPTH Feet	PRESSURE Psig	GRADIENT Psi/Ft.
0	1784	
1000	1834	0.050
2000	1885	0.051
3000	1941	0.056
4000	1992	0.051
5000	2044	0.052
5500	2070	0.052
5600	2074	0.040
5700	2080	0.060
5800	2086	0.060
5900	2091	0.050
6000	2095	0.040
6100	2101	0.060
6200	2106	0.050
6300	2112	0.060
6400	2118	0.060
6500	2124	0.060

PRESSURE POUNDS PER SQUARE INCH GAUGE



STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

SUBMIT IN TRIPLICATE*
(Other instructions on
reverse side)

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug a well or to change a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. St. Of UT-ML 42673	
2. NAME OF OPERATOR MITCHELL ENERGY CORPORATION		6. IF INDIAN, ALLOTTEE OR TRIBE NAME NA 123019	
3. ADDRESS OF OPERATOR 1670 Broadway - Suite 3200 Denver, CO 80202		7. UNIT AGREEMENT NAME NA SGW-DKTA	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface 1217' FWL & 863' FSL (SWSW)		8. FARM OR LEASE NAME Hell's Hole State	
14. PERMIT NO. 43-047-31802		9. WELL NO. 1-36-10-25	
15. ELEVATIONS (Show whether OF, RT, OR, etc.) 5820' GR		10. FIELD AND POOL, OR WILDCAT Hell's Hole	
		11. SEC. T., R., M., OR BLK. AND SURVEY OR AREA Sec. 36-T10S-R25E	
		12. COUNTY OR PARISH Uintah	13. STATE UT

DEC 28 1987

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐

(Other) Build Pit

PULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐ABANDON ☐CHANGE PLANS ☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☐(Other) ☐REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT ☐

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

This is sent to confirm our phone conversation with Ron Firth on 12/22/87 authorizing Mitchell Energy Corporation to construct a blow down pit for emergency use on the subject location. The pit will be used primarily while cutting parafin.

18. I hereby certify that the foregoing is true and correct

SIGNED James C. Anderson
JAMES C. ANDERSON

TITLE District Production Manager DATE 12/22/87

(This space for Federal or State office use)

APPROVED BY _____
CONDITIONS OF APPROVAL, IF ANY:

TITLE _____

DATE _____

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

SUBMIT IN TRIPLICATE*
(Other instructions on
reverse side)

SCW 10KTA

SUNDRY NOTICES AND REPORTS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

MAR 14 1988

1. OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. St of UT-ML 42673
2. NAME OF OPERATOR MITCHELL ENERGY CORPORATION		6. IF INDIAN, ALLOTTEE OR TRIBE NAME NA 031517
3. ADDRESS OF OPERATOR 555 17th Street - Suite 3500 Denver, CO 80202		7. UNIT AGREEMENT NAME NA
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 1217' FWL & 863' FSL (SWSW)		8. FARM OR LEASE NAME Hell's Hole State
14. PERMIT NO. 43-047-31802		9. WELL NO. 1-36-10-25
15. ELEVATIONS (Show whether OF, ST, GR, etc.) 5820' GR		10. FIELD AND POOL, OR WILDCAT Hell's Hole
		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 36-T10S-R25E
		12. COUNTY OR PARISH Uintah
		13. STATE UT

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐(Other) ☐FULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐ABANDON* ☐CHANGE PLANS ☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☐(Other) ☐REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT* ☐

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

As of February 2, 1988 the Hell's Hole State #1-36-10-25 well is temporarily SHUTIN, waiting on design and installation of artificial lift equipment.

18. I hereby certify that the foregoing is true and correct

SIGNED James C. Anderson
JAMES C. ANDERSON

TITLE District Production Manager

DATE 3/11/88

(This space for Federal or State office use)

APPROVED BY _____

TITLE _____

DATE _____

CONDITIONS OF APPROVAL, IF ANY:

May 31, 1988

RECEIVED
JUN 2 1988

DIVISION OF
OIL, GAS & MINING

UTAH DIVISION OF OIL, GAS AND MINING
#3 Triad Center - Suite 350
Salt Lake City, Utah 84180-1203

Attn: Mr. John Maza

Re: Hell's Hole State 1-36-10-25
Uintah County, Utah



Dear John:

Pursuant to your phone conversation of May 27, 1988 with Mark McNamee please find the attached Sundry Notice requesting permission to flare gas during a well test on the subject well. We would like to test the well for 30 days through the month of June to obtain an accurate stabilized rate.

Your cooperation in this matter is appreciated.

Sincerely,

MITCHELL ENERGY CORPORATION

James C. Anderson

James C. Anderson
District Production Manager

JCA/MM/jms
Encl.

CONFIDENTIAL

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MININGRECEIVED
JUN 2 1988

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug wells. Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		7. UNIT AGREEMENT NAME NA	
2. NAME OF OPERATOR MITCHELL ENERGY CORPORATION		8. FARM OR LEASE NAME HELL'S HOLE STATE	
3. ADDRESS OF OPERATOR 555 17th Street - Suite 3500 Denver, CO 80202		9. WELL NO. 1-36-10-25	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 863' FSL & 1217' FWL (SWSW)		10. FIELD AND POOL, OR WILDCAT Hell's Hole	
14. PERMIT NO. 43-047-31802		12. COUNTY OR PARISH Uintah	
15. ELEVATIONS (Show whether OF, RT, GR, etc.) 5820' GR		13. STATE UT	

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETION <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>
(Other) Production test <input type="checkbox"/>	

SUBSEQUENT REPORT OF:

WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
(Other) <input type="checkbox"/>	

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

This well was originally completed as a GAS WELL on 10/22/87. However it proved incapable of producing as a gas well and was placed on rod pump on 5/14/88. While testing the well the oil was produced to the stock tank the the gas placed in our gathering system. Due to the fact that our gas sales are shut-off due to lack of market demand we are forced to begin flaring gas while testing this well. We would like your permission to flare gas from this well for a one month well test. The test is necessary so that we can properly size our production facilities. The well is currently producing + 80 BOPD and 110 mcf/d.

CONFIDENTIAL

18. I hereby certify that the foregoing is true and correct

SIGNED James C. Anderson
JAMES C. ANDERSONTITLE District Production Manager DATE 5/31/88

(This space for Federal or State office use)

APPROVED BY _____
CONDITIONS OF APPROVAL, IF ANY:

TITLE _____

DATE _____

June 24, 1988

STATE OF UTAH
Division of Oil, Gas & Mining
#3 Triad Center - Suite 350
Salt Lake City, Utah 84180-1203

Attn: Mr. John Baza

RECEIVED
JUN 27 1988

**DIVISION OF
OIL, GAS & MINING**

Re: Hell's Hole State #1-36-10-25
Uintah County, Utah



Dear John:

Please find the attached Sundry Notice requesting an extension of the well test flow period. This extension is necessitated by complications due to gas contract requirements. Additional tests are required to obtain an accurate deliverability and lease equipment which guarantees an allowable gas quality.

Sincerely,

MITCHELL ENERGY CORPORATION

Mark McManis
FOR

James C. Anderson
District Production Manager

JCA/MM/jms
Encl.

CONFIDENTIAL

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

SUBMIT IN TRIPLICATE
(Only instructions on reverse side)

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such.)

1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. St. of UT-ML 42673	
2. NAME OF OPERATOR MITCHELL ENERGY CORPORATION		6. IF INDIAN, ALLOTTEE OR TRIBE NAME NA	
3. ADDRESS OF OPERATOR 555 17th Street - Suite 3500 Denver, CO 80202		7. UNIT AGREEMENT NAME NA	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface 863' FSL & 1217' FWL (SWSW)		8. FARM OR LEASE NAME Hell's Hole State	
14. PERMIT NO. 43-047-31802		9. WELL NO. 1-36-10-25	
15. ELEVATIONS (Show whether OF, RT, GR, etc.) 5820' GR		10. FIELD AND POOL, OR WILDCAT Hell's Hole	
		11. SEC., T., R., M., OR BLK. AND SURVEY OR ABBA Sec. 36-T10S-R25E	
		12. COUNTY OR PARISH Uintah	
		13. STATE UT	

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐(Other) PRODUCTION TEST ☐PULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐ABANDON* ☐CHANGE PLANS ☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☐(Other) ☐REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT* ☐

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.) *

MITCHELL ENERGY CORPORATION needs your permission to continue flaring gas from this well for well test purposes. The current gas purchaser requires more accurate deliverability data before issuing a gas contract. Mitchell also needs the extended time to acquire the properly sized lease equipment and install it. The well is currently producing 80+ BOPD & 180 MCFD.

CONFIDENTIAL

18. I hereby certify that the foregoing is true and correct

SIGNED

Mark McNamee FOX
JAMES C. ANDERSON

TITLE

DISTRICT PRODUCTION MANAGER

DATE 6/24/88

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE


CONDITIONS OF APPROVAL, IF ANY:

*See Instructions on Reverse Side

John R. Baya
7-11-88

Hells Hole Stack 1-36 sec 36, T105, R85E Hubby 11/29/88

N



3160
(U-922)

June 30, 1992

Mitchell Energy Corp.
P.O. Box 4000
Woodlands, TX 77387-4000
Attn: Jerry Taylor

Re: Determinations for Pre-Unit
Wells, Hells Hole Unit
Uintah County, Utah

Gentlemen:

Pursuant to telephone conversation between Mickey Coulthard, Bureau of Land Management, and Jerry Taylor, Mitchell Energy, it has been determined by this office that under existing conditions the following Unit wells are not capable of producing unitized substances in paying quantities as defined in Section 9 of the unit agreement. Production from these wells shall be handled and reported on a lease basis

2-36-10-25 NE $\frac{1}{4}$ NE $\frac{1}{4}$ Section 36 Township 10 South Range 25 East
1-36-10 SW $\frac{1}{4}$ SW $\frac{1}{4}$ Section 36 Township 10 South Range 25 East

43-047-31803

If you have any question please contact Mickey Coulthard of this office at (801)539-4042.

Sincerely,

(Orig. Sgd.) R. A. Henricks

Robert A. Henricks
Chief, Branch of Fluid Minerals

bcc: DM Vernal
Hell's Hole Unit File
Agr. Sec. Chron.
U-942
Fluid Chron
MMS RMP-Reference Data Branch (ATTN Richard Richards)
Division of Oil Gas and Mining
Tickler (July)

MCoulthard:mc:6/30/92

RECEIVED

JUL 02 1992

DIVISION OF
OIL GAS & MINING



SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL ☒ GAS ☐ OTHER:

2. Name of Operator:

Mitchell Energy Corporation

3. Address and Telephone Number:

P.O. Box 4000, The Woodlands, Texas 77387-4000 (713)377-5815

4. Location of Well

Footages: 1217' FWL and 863' FSL (SW SW)

CO, Sec., T., R., M.: Sec. 36, T20S, R25E

5. Lease Designation and Serial Number:

U-42673

6. If Indian, Allocated or Tribe Name:

N/A

7. Unit Agreement Name:

N/A

8. Well Name and Number:

Hell's Hole
State Well No. 1-36-10-25

9. API Well Number:

43-047-31802

10. Field and Pool, or Wildcat:

Hell's Hole Canyon

County: Uintah

State: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT

(Submit in Duplicate)

- | | |
|--|---|
| <input type="checkbox"/> Abandonment | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recompletion |
| <input type="checkbox"/> Conversion to Injection | <input type="checkbox"/> Shoot or Acidize |
| <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other _____ | |

Approximate date work will start _____

SUBSEQUENT REPORT

(Submit Original Form Only)

- | | |
|--|---|
| <input type="checkbox"/> Abandonment | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Shoot or Acidize |
| <input type="checkbox"/> Conversion to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other <u>Status (Record Purposes Only)</u> | |

Date of work completion _____

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

ANNUAL STATUS REPORT

Due to downhole pump problems, the subject well ceased to produce on September 19, 1993.
The well is currently under evaluation.

13.


Name & Signature: Doris A. Zajac

Doris A. Zajac

Title: REG. Affairs SpecialistDate: 2-16-95

(This space for State use only)

February 16, 1995



Mr. Don T. Staley
Administrative Manager, Oil and Gas
State of Utah
Department of Natural Resources
355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203



RE: Annual Status Reports
H. H. Federal Well No. 1-12-11-25
Hell's Hole Unit Well No. 1-26-10-25
Hell's Hole State Well No. 1-36-10-25
Hell's Hole State Well No. 2-36-10-25
Uintah County, Utah

Dear Mr. Staley:

Enclosed in duplicate, please find the annual status reports for the captioned wells. Should you require additional information, please call me at (713) 377-5815.

Very truly yours,

MITCHELL ENERGY CORPORATION

A handwritten signature in black ink, reading "Doris A. Zajac". The signature is fluid and cursive, with the last name "Zajac" being more prominent.

Doris A. Zajac
Regulatory Affairs Specialist

utahsun.daz

Enclosures

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL ☒ GAS ☐ OTHER:

2. Name of Operator:
Mitchell Energy Corporation

3. Address and Telephone Number:
P.O. Box 4000, The Woodlands, Texas 77387-4000 (713)377-5815

4. Location of Well
Footages: 1217' FWL and 863' FSL (SW SW)
QQ, Sec., T., R., M.: Sec. 36, T10S, R25E

5. Lease Designation and Serial Number:

ML-42673

6. If Indian, Allottee or Tribe Name:

N/A

7. Unit Agreement Name:

N/A

8. Well Name and Number:

Hell's Hole State
Well No. 1-36-10-25

9. API Well Number:

43-047-31802

10. Field and Pool, or Wildcat:

Hell's Hole Canyon

County: Uintah

State: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT

(Submit in Duplicate)

- | | |
|--|---|
| <input checked="" type="checkbox"/> Abandonment | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recompletion |
| <input type="checkbox"/> Conversion to Injection | <input type="checkbox"/> Shoot or Acidize |
| <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other | |

Approximate date work will start

SUBSEQUENT REPORT

(Submit Original Form Only)

- | | |
|--|---|
| <input type="checkbox"/> Abandonment | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Shoot or Acidize |
| <input type="checkbox"/> Conversion to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other | |


Date of work completion

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Mitchell Energy Corporation intends to plug and abandon the subject well in July or August, 1995 when supervisory personnel are available to oversee the plugging operations. The plugging procedure is attached for your approval. This well is currently inactive.



Approved
by the
Utah Division of
Oil, Gas and Mining
as per attached steps

13. Name & Signature: Doris A. Zajac Doris A. Zajac Title: Reg. Affairs Specialist Date: 6-8-95

(This space for State use only)

P&A PROCEDURE
H. H. STATE #1-36-10-25

H.H. State #1-36-10-25	Perfs: 6467-6489' 6490-6505'	AFE No. B5907
Hell's Hoke (Dakota)		WIO: 100% MEC
Uintah County, Utah	PKR:	Surf Csg: 8-5/8" @ 802'
Area III	CIBP:	Prod Csg: 4-1/2" @ 6830'
	RBP: 6384'	Other: DV Tool @ 3521'
TD 6830'	SN: 6517'	
PBTD 6717'	EOT: 6548'	
Loc. No. 05071-01-1		
Objective: Plug and Abandon		

1. MI and RU workover unit. Blow well down.
2. POOH with rods and pump. Install BOP.
3. Release TA at 6384' and POOH with 2-3/8" tubing and TA.
4. RU wireline service company. GIH with gauge ring to $\pm 6450'$. GIH with CIBP and set at $\pm 6400'$. Test CIBP to 500 psi. Dump bail three sacks of Class "H" neat cement on top of CIBP (35' cement fill).
5. GIH with 2-3/8" tubing to $\pm 6300'$ and circulate hole with 9.0 ppg saltwater.
6. PUH to 3571' and set a 10 sack Class "H" neat balanced cement plug from 3570' up to 3470'.
7. PUH with tubing to 50' and set a 5-10 sack Class "H" neat cement plug from 50' to the surface. Pressure test 4-1/2" x 8-5/8" annulus to 200 psi*.
8. Cut off casing 3' below ground level and weld a 1/2" steel plate cap on the wellbore with the required well information.
9. RD&MOL. Proceed with surface reclamation according to BLM specifications.

- * If the annulus does not pressure test be prepared to pump a 15 sack Class "H" neat cement plug (50' cement fill) into the annulus. (The annulus must pressure test or the plug must be visible at the surface!).

Note: Send all downhole and wellhead equipment to the MEC Rabbit Mountain yard for future use.

Rick Wilson *REW*

REW/tkb: C:\WP51DATA\REW\STATE1-3.PRC
01-17-95 *lfw*

Approved: *W S Buckler*
Workover Superintendent

Date: 1-27-95



State of Utah

DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Ted Stewart
Executive Director

James W. Carter
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340
801-359-3940 (Fax)
801-538-5319 (TDD)

PLUG AND ABANDONMENT STIPULATIONS
FOR HELL'S HOLE STATE 1-36-10-25
SECTION 36, TOWNSHIP 10 SOUTH, RANGE 25 EAST
UINTAH COUNTY, UTAH
API # 43-047-31802

1. In Step 5, hole should be filled with a non corrosive fluid as per R649-3-24-3.4. (this can be like a packer fluid, ie. water with an oxygen scavenger and corrosion inhibitor.)
2. Set a balanced cement plug from \pm 850' to 750'.
3. Set 10 sx. plug at surface and fill all annuli to surface with cement.



WELLBORE DIAGRAM

WELL NAME: H. H. STATE NO. 1-36-10-25 DATE: 07-29-93 PRES: X PROP: _____
 AREA: III DEPT: 475 LOC NO: 05071-01-1 FIELD: HELL'S HOLE FIELD
 STATE: UTAH COUNTY: UINTAH GAS/OIL PURCH: MT. FUEL/ENRON
 COMP: N/A LSE OPER: N/A PREP BY: LARRY LINDSEY
 TD: 6830' PBTD: 6717' SPUD: 09-01-87 COMPL: 10-07-87 INIT DELV: 11-30-87

14" COND
PPE @ 40'

KB: 5833' DF: _____ GL: 5820' MEC GWI: _____ MEC NRI: _____

SURFACE CASING

DEPTH	SIZE	WT	GRADE
802'	8-5/8"	24#	K-55
BIT SIZE		SACKS	TOC
12-1/4"		560	SURF

PERFORATIONS

DATE	FROM	TO	SHOTS	STATUS
10-04-87	6490'	6505'	31	PROD
10-06-87	6467'	6489'	45	PROD
10-10-87	6467'	6489'	23	PROD

TUBING MAKEUP

3521' CMT THRU DV TOOL TO SURF w/ 1015 SKS CMT.

TBG SIZE	DEPTH	WT	GRADE
2-3/8"	6548'	4.7#	J-55
COUPLINGS		DRIFT	DATE RUN
8rd EUE		1.901"	12-02-89

PACKERS & PLUGS

DEPTH	TYPE	DATE SET
6384'	TBG ANCHOR	12-02-89

ROD MAKEUP

4	7/8" ROD SUBS(2',4',6',8')
75	7/8" SUCKER RODS
184	3/4" SUCKER RODS
1	1 1/2" 20' PUMP w/ CHRM BBL

TOC @ 5300'

DAKOTA

6384' TUBING ANCHOR

6467' ACIDIZE PERFS 6467-6505' w/ 1000 GALS 7 1/2%
 68 MSR-100 ACID w/ 500 scf/bbl N2 ASSIST (10-7-87).
 HOLES FRAC PERFS 6467-6505' w/ 25,800 GALS 70% QUALITY
 6489' CO2 FOAM + 85,000# 20/40 SAND (10-11-87).
 6490' PUMP 121 BC w/ PARAFFIN SOLVENT (8-10-88).
 31
 HOLES ACIDIZE PERFS 6490-6505' w/ 1500 GALS 7 1/2%
 6505' MSR-100 ACID @ 5 BPM w/ 3180 psi(10-5-87).
 6548' NOTCHED COLLAR ON EOT w/ SN AT 6517'.
 6568' PUSHED BAKER PACKER FROM 6307' (5-14-88).
 6717' PBTD

PRODUCTION CASING

DEPTH	SIZE	WT	GRADE	CLASS	BIT SIZE	SACKS	TOC
6830'	4-1/2"	11.6#	K-55	A	7-7/8"	890	5300'
DV TOOL: 3521'						1015	SURF

WELLBORE DIAGRAM

WELL NAME: H. H. STATE NO. 1-36-10-25 DATE: 01-13-95 PRES: _____ PROP: X
 AREA: III DEPT: 475 LOC NO: 05071-01-1 FIELD: HELL'S HOLE FIELD
 STATE: UTAH COUNTY: UINTAH GAS/OIL PURCH: MT. FUEL/ENRON
 COMP: N/A LSE OPER: N/A PREP BY: RICK WILSON
 TD: 6830' PBTD: 6717' SPUD: 09-01-87 COMPL: 10-07-87 INIT DELV: 11-30-87

14" COND
PIPE @ 40'

KB: 5833' DF: _____ GL: 5820' MEC GWI: 1.00 MEC NRI: _____

SURFACE CASING

DEPTH	SIZE	WT	GRADE
802'	8-5/8"	24#	K-55
BIT SIZE		SACKS	TOC
12-1/4"		560	SURF

PERFORATIONS

DATE	FROM	TO	SHOTS	STATUS
10-04-87	6490'	6505'	31	PA
10-06-87	6467'	6489'	45	PA
10-10-87	6467'	6489'	23	PA

ALL CASING TO BE CUT OFF 3' BELOW
GROUND LEVEL WITH A 1/2" PLATE WELDED
ON TOP.

TUBING MAKEUP

TBG SIZE	DEPTH	WT	GRADE
----------	-------	----	-------

COUPLINGS	DRIFT	DATE RUN
-----------	-------	----------

PACKERS & PLUGS

DEPTH	TYPE	DATE SET
6400'	CIBP W/ 35' CMT	
3570'-3470'	CMT PLUG	
50'-3'	CMT PLUG	

TOC @ 5300'

3521' CMT THRU DV TOOL TO SURF w/ 1015 SKS CMT.

<-----CEMENT PLUG SET FROM 3570'-3470'

<-----PROD. CASING LOADED WITH 9.0 PPG FLUID

DAKOTA

6400' CIBP SET AT 6400' WITH ^{35'} 400' OF CMT.

6467' ACIDIZE PERFS 6467-6505' w/ 1000 GALS 7 1/2%

68 MSR-100 ACID w/ 500 scf/bbl N2 ASSIST (10-7-87).

HOLES FRAC PERFS 6467-6505' w/ 25,800 GALS 70% QUALITY

6489' CO2 FOAM + 66,000# 20/40 SAND (10-11-87).

6490' PUMP 121 BC w/ PARAFFIN SOLVENT (8-10-88).

31

HOLES ACIDIZE PERFS 6490-6505' w/ 1500 GALS 7 1/2%

6505' MSR-100 ACID @ 5 BPM w/ 3180 psi (10-5-87).


6548' NOTCHED COLLAR ON EOT w/ SN AT 6517'.

6568' PUSHED BAKER PACKER FROM 6307' (5-14-88).

6717' PBTD

PRODUCTION CASING

DEPTH	SIZE	WT	GRADE	CLASS	BIT SIZE	SACKS	TOC
6830'	4-1/2"	11.6#	K-55	A	7-7/8"	890	5300'
DV TOOL: 3521'						1015	SURF



SUNDRY NOTICES AND REPORTS ON WELLS **DIV. OF OIL, GAS & MINING**

Do not use this form for proposals to drill new wells, deepen existing wells, or to recomplete plugged and abandoned wells.
 Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL ☒ GAS ☐ OTHER:

2. Lease Designation and Serial Number:

U-42673

3. If Indian, Allottee or Tribe Name:

N/A

4. Unit Agreement Name:

N/A

5. Well Name and Number: Hell's Hole
 State #1-36-10-25

6. API Well Number:

43-047-31802

7. Field and Pool, or Wildcat:

Hell's Hole Canyon

8. Address and Telephone Number:

P.O. Box 4000, The Woodlands, TX 77387-4000 (713) 377-5815

9. Location of Well

Footages: 1217' FWL and 863' FSL (SW SW)

County: Uintah

State: Utah

QQ, Sec. T., R., M.: Sec. 36, T10S, R25E

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT

(Submit in Duplicate)

- | | |
|--|---|
| <input type="checkbox"/> Abandonment | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recompletion |
| <input type="checkbox"/> Conversion to Injection | <input type="checkbox"/> Shoot or Acidize |
| <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other _____ | |

Approximate date work will start _____

SUBSEQUENT REPORT

(Submit Original Form Only)

- | | |
|--|---|
| <input checked="" type="checkbox"/> Abandonment | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Casing Repair | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Shoot or Acidize |
| <input type="checkbox"/> Conversion to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other _____ | |

Date of work completion _____

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION AND LOG form.

* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

The subject well was plugged and abandoned on June 22, 1995 as per the attached chronology. Also attached is a wellbore sketch of the P&A'd well.

13.

Name & Signature:

Rick Wilson

Rick Wilson

Title: Staff Production Engineer 7-11-95

(This space for State use only)

HELL'S HOLE (Dakota)
Uintah Co. UT
TD 6830'
PBDT 6717'

Perfs
CIBP 6390' (w/35' cmt)
6467-6489'
6490-6505'

H. H. State #1-36-10-25
AFE No. B5907
WIO: 100% MEC
8-5/8" set at 802'
4-1/2" set at 6830'
DV tool at 3521'

OBJECTIVE: Plug and abandon well.

06-19-95 MI & RU Temple Well Service Rig #1. SITP 0 psi. SICP 320 psi. Unhung rods. Unable to unseat pump. Backed off rods. POH laying down 1-1/2" x 26' spray metal polished rod, 7/8" x 2' rod sub, 75 - 7/8" rods with guides and 55 - 3/4" rods with guides. WIH with swab to top of rods at ±3250' recovering 20' oil. Blew casing down to a strong gas blow and heavy mist of oil on an open choke recovering 20 bbls in 6 hrs. RU Nowco. Killed well with 25 bbls 2% KCl water. Unflanged wellhead. Released TA at 6384'. NU BOP. POH with 92 jts 2-3/8" tubing with TA (swinging) at 3556', SN at 3689' and EOT at 3720' to thick paraffin cut oil in tubing. Unable to swab. SWI and SDFN. TR well 20/25.

Daily Cost \$5,057

Cost to Date \$5,057

AFE Est. Cost \$15,000

Loc 0507101

06-20-95 SITP 0 psi. SICP 200 psi. RU Adler Hot Oil Service. Pumped 50 bbls hot 2% KCl water down 2-3/8" - 4-1/2" annulus establishing returns out of 2-3/8" tubing (cleaning remaining rods and tubing). Swabbed well down to rods in tubing. POH with 15 jts 2-3/8" tubing to rods. Attempted to unseat pump. Backed off rods. POH with 8 - 3/4" rods with guides and 48 rods (no guides) with rod box on bottom. Swabbed well down to rods in tubing. POH with 45 jts 2-3/8" tubing. Backed off rods. POH with 9 - 3/4" rods. Backed off rods. POH with 34 - 3/4" rods. Swabbed well down. POH with 27 jts 2-3/8" tubing to rods. Backed off rods. POH with 21 - 3/4" rods. Swabbed well down. POH with 17 jts 2-3/8" tubing to rods. Backed off rods. POH with 9 - 3/4" rods. Swabbed well down. POH with 4 jts 2-3/8" tubing. Baker 4-1/2" x 2-3/8" TA, 4 jts 2-3/8" tubing, SN and 1 jt 2-3/8" tubing. Found 2" x 1-1/2" x 20' pump with 6" strainer nipple stuck in joint above SN. WIH with 1" x 2" swage, SN and 114 jts 2-3/8" tubing to 3500'. SWI and SDFN. TR Well 20/115.

Daily Cost \$3,847

Cost to Date \$8,904

AFE Est. Cost \$15,000

Loc 0507101

06-21-95 SITP 20 psi. SICP 40 psi. Blew well down. WIH with 55 - 3/4" rods with guides and 75 - 7/8" rods with guides. RU Adler Hot Oil Service. Pumped 20 bbls hot 2% KCl water down tubing to clean rods. POH laying down rods. WIH with 120 - 3/4" rods. POH laying down rods. (Rods on location - 75 - 3/4" rods with guides, 63 - 3/4" rods with guides and 121 - 3/4" rods without guides). POH with 114 jts 2-3/8" tubing, SN and swage. RU Oil Well Perforators. Ran 3.625" OD gauge ring to 6465'. Set 4-1/2" Baker Model 5-1AA 10K CIBP at 6390'. Loaded casing with 57 bbls 2% KCl water. Tested casing and CIBP to 500 psi. Dump bailed 3 sks of cement on top of CIBP (35' cmt fill). RD OWP. SWI and SDFN. Note: Operations witnessed by David Hackford from the State of Utah Department of Natural Resources Division of Oil, Gas & Mining. TR well 38/135.

Daily Cost \$7,587

Cost to Date \$16,491

AFE Est. Cost \$15,000

Loc 0507101

06-22-95 SICP 0 psi. WIH with 2-3/8" SN and 205 jts 2-3/8" tubing to 6293'. RU BJ Services. Circulated hole with 2% KCl water and packer fluid. POH laying down 89 joints 2-3/8" tubing with EOT at 3566'. Pumped and spotted 10 sacks Class "G" neat balanced cement plug (1.14 cf/sk, 15.8 ppg, 5.0 gals H₂O/sk) from 3566' up to 5470'. POH laying down 89 joints 2-3/8" tubing with EOT at 844'. Pumped and spotted 10 sacks Class "H" neat balanced cement plug from 844' to 744'. POH laying down 27 joints 2-3/8" tubing. ND BOP and tubinghead. WIH with 4 jts 2-3/8" tubing with EOT at 123'. Pumped 10 sack Class "H" neat cement plug from 123' to surface. Welder cut off bradenhead and casing. Filled annulus to surface with 2 sacks Class "G" neat cement. Welded steel plate cap on wellbore with 4" OD x 4' pipe above ground level welded to cap with required well information on pipe. RD Temple Rig #1 and MOL. Well P&A'd. (Note: P&A operations witnessed by David Hackford from State of Utah Department of Natural Resources Division of Oil, Gas and Mining).

Daily Cost \$7,291

Cost to Date \$23,782

AFE Est. Cost \$15,000

Loc 0507101

06-23-95 FINAL REPORT!

Daily Cost \$-0-

Cost to Date \$23,782

AFE Est. Cost \$15,000

Loc 0507101

WELLBORE DIAGRAM

WELL NAME: H. H. STATE NO. 1-36-10-25 DATE: 07-29-93 PRES: _____ PROP: _____
 AREA: III DEPT: 475 LOC NO: 05071-01-1 FIELD: HELL'S HOLE FIELD
 STATE: UTAH COUNTY: UINTAH GAS/OIL PURCH: MT. FUEL/ENRON
 COMP: N/A LSE OPER: N/A PREP BY: R. WILSON
 TD: 6830' PBTD: 6717' SPUD: 09-01-87 COMPL: 10-07-87 INIT DELV: 11-30-87

14" COND
PIPE @ 40'

KB: 5833' DF: _____ GL: 5820' MEC GWI: 1.000 MEC NRI: _____

SURFACE CASING

DEPTH	SIZE	WT	GRADE	DATE	FROM	TO	SHOTS	STATUS
802'	8-5/8"	24#	K-55	10-04-87	6490'	6505'	31	PA'D
BIT SIZE SACKS TOC				10-06-87	6467'	6489'	45	PA'D
	12-1/4"	560	SURF	10-10-87	6467'	6489'	23	PA'D

PERFORATIONS

CEMENT PLUG (10 SACKS) SET AT 123' UP TO SURFACE

CEMENT PLUG (10 SACKS) SET AT 844' UP TO 744'

TUBING MAKEUP

3521' CMT THRU DV TOOL TO SURF w/ 1015 SKS CMT.
CEMENT PLUG (10 SACKS) SET AT 3586' UP TO 3470'

TBG SIZE	DEPTH	WT	GRADE
N/A			
COUPLINGS	DRIFT	DATE RUN	

PACKERS & PLUGS

DEPTH	TYPE	DATE SET
6390'	CIBP (W/ 35' CMT)	06-21-95

6390' CIBP WITH 35' OF CEMENT

6467' ACIDIZE PERFS 6467-6505' w/ 1000 GALS 7 1/2%
 68 MSR-100 ACID w/ 500 scf/bbl N2 ASSIST (10-7-87).
 HOLES FRAC PERFS 6467-6505' w/ 25,800 GALS 70% QUALITY
 6489' CO2 FOAM + 66,000# 20/40 SAND (10-11-87).
 6490' PUMP 121 BC w/ PARAFFIN SOLVENT (8-10-88).
 31
 HOLES ACIDIZE PERFS 6490-6505' w/ 1500 GALS 7 1/2%
 6505' MSR-100 ACID @ 5 BPM w/ 3180 psi (10-5-87).

WELL P&A'D ON 06-22-95

6548' NOTCHED COLLAR ON EOT w/ SN AT 6517'.

6568' PUSHED BAKER PACKER FROM 6307' (5-14-88).

6717' PBTD

PRODUCTION CASING

DEPTH	SIZE	WT	GRADE	CLASS	BIT SIZE	SACKS	TOC
6830'	4-1/2"	11.6#	K-55	A	7-7/8"	890	5300'
DV TOOL: 3521'						1015	SURF

TOC @ 5300'

DAKOTA

